

November 21, 2017

Quote #: Q-WCHI-12212

Tom Cane
City of Aurora
44 E Downer Place
Aurora IL 60507

RE: COA-Downer Place Fiber Connections

Mr. Cane,

Thank you for the opportunity to submit the following proposal for the project referenced above.

1. Furnish & install (7) outdoor wall mount fiber patch panel boxes at various locations
2. Furnish & install approximately 800 ft of 96 count outdoor armored fiber from the last building to the feed building
3. Core feed building and run cable into IT room
4. Furnish & install (1) 4U rack mount FDP in the IT room
5. Furnish (2) 12 count pigtails, (2) trays and terminate (24) fibers
6. Midsheath the 96 count cable in (6) of the (7) wall boxes in preparation of future use
7. Prep the tail of the 7th box for future use
8. Provide trucks, bucket trucks and Fusion splicer

Labor and Equipment Total:

\$14,996.00

Notes:

- Excludes permits
- All work will take place during normal business hours
- This quote does not include bulkheads, or trays in the tenant wall boxes
- Terminations in tenant wall boxes are not included in this quote
- Cable will be attached without conduit on the exterior of all buildings and will follow an existing aerial path between buildings

We appreciate the opportunity to provide your company with a proposal and hope to work with you on this project. Should you have any questions or if we can be of further assistance, please call me at the number below.

Sincerely,

Rick Danca

National Technologies NTI
1350 W Washington St
West Chicago, IL 60185
CELL (630)915-5164
EMAIL: rdanca@ntifiber.com