

Property Research Sheet

Location ID#(s): 21801

As of: 1/22/2018

Researched By: Jill Morgan

Address: 260 S LaSalle St

Current Zoning: R4

Parcel Number(s): 15-27-104-019

1929 Zoning: B Residential Districts

Subdivision: Lot 8 of Robinsons Subdivision

1957 Zoning: R-4 Two-Family Dwelling District

Size: 0.13 Acres / 5,663 Sq. Ft.

Comp Plan Designation: Low Density Residential

School District: SD 131 - East Aurora School District

ANPI Neighborhood: McCarty Burlington

Park District: FVPD - Fox Valley Park District

TIF District: N/A

Ward: 2

Historic District: None

Current Land Use

Current Land Use: Residential: Duplex

AZO Land Use Category: Two Family Dwelling (1120)

Number of Buildings: 1

Number of Stories: 2

Building Built In:

Total Dwelling Units: 2

Total Building Area: 1,228 sq. ft.

Residential Rental: 0 / License:

Zoning Provisions

Setbacks and Other Bulk Standards:

Requirements are pursuant to the Aurora Zoning Ordinance Section(s) 5 and 7.8.

Setbacks are typically as follows:

Front Yard Setback: 30 feet or

Side Yard Setback: 6 feet on lots less than 60 feet wide or less or 8 feet on lots greater than 60 feet

Exterior Side Yard Setback: 10 feet

Exterior Side Yard Reverse Corner Setback: 15 feet

Rear Yard Setback: 20 feet

Exterior Rear Yard Setback: 20 feet

Setback Exceptions: Front setback exception for an infill lot. On infill lots the public street elevation of the structure shall be located at the average established setback line of the Impact

Area. For additional regulations on infill lots refer to Infill Housing Standards located in the Residential District Specific Regulations of the zoning ordinance.

Side setback exception for religious institutions: On lots upon which a religious institution is constructed or extensions made to an existing religious institution, there shall be a side setback line of not less than ten (10) feet on each side of the main structure and a combined total of side setback of not less than twenty-five (25) feet.

Interior Drive Yard Setback: none

Other bulk standards are typically as follows:

Building Separations: None

Minimum Lot Width and Area: Typically 60 feet and 8,000 sq ft

Exception: One-family and Religious Institutions: 75 feet and 10,000 sq ft

Maximum Lot Coverage: 40%

Maximum Structure Height: Typically 35 feet and not over 2 ½ stories.

Floor Area Ratio: None

Minimum Primary Structure Size: Typically 2,400 sq ft

Minimum Dwelling Unit Size: Typically 1,000 sq ft

Maximum Density: None

Parking and Loading:

The Parking and Loading requirements are pursuant to the Aurora Zoning Ordinance Table Two: Schedule of Off-street Parking Requirements and Section(s) 5 and 7.8.

Permitted Uses:

Permitted Uses are pursuant to the Aurora Zoning Ordinance Table One: Use Categories and Section(s) 4.2 and 7.8 Permitted Exceptions:

Special Uses:

Special Uses are pursuant to the Aurora Zoning Ordinance Table One: Use Categories and Section(s) 4.3 and 7.8.

Limited But Permitted Uses:

Limited but Permitted Uses are pursuant to the Aurora Zoning Ordinance Table One: Use Categories and Section(s) 4.3 and 7.8.

Miscellaneous Notes on History

None

Legislative History

The known legislative history for this Property is as follows:

O1957-3100 approved on 11/4/1957: AURORA ZONING ORDINANCE AND MAP.

O1978-4739 approved on 7/18/1978: AN ORDINANCE AMENDING ORDINANCE NO.3100 BEING THE AURORA ZONING ORDINANCE, AND THE ZONING MAP ATTACHED THERETO.

Location Maps Attached:


Aerial Overview

Location Map

Zoning Map

Comprehensive Plan Map

Aerial Map (1:1,000):



S Lasalle St

North Av

S Lincoln Av


Legend

 Subject Property

 Planning & Zoning Division

N 

Comprehensive Plan (1:5,000):



Legend

Comprehensive Plan

- River/Lakes/Ponds/Streams
- Public
- Quasi - Public
- Conservation, Open Space, Recreation, Drainage
- Estates
- Low Density Residential
- Medium Density Residential
- High Density Residential
- Office
- Commercial
- Mixed Uses: Office/Research/Commercial
- Office/Research/Light Industrial
- Mixed Uses: Offices/Research/Commercial/Residential
- Industrial
- Utilities
- Subject Property

N
 Planning & Zoning Division

Location Map (1:1,000):

