

January 6, 2022

Quote #: Q-CHI-N42320

Mike Baker
City of Aurora
44 E Downer Place
Aurora IL 60507

RE: Well 29-1374 Deerpath

Mr Baker,

Thank you for the opportunity to submit the following proposal for the project referenced above.

1. Furnish and install approx 4,000' of 1.25 polyduct with tracer and mule line from existing HH 7-2 to new location at Well 29 at 1374 Deerpath Rd.
2. Furnish and install (4) 30" x 48" HH's and (4) Peds along route.
3. Furnish and install RGS riser conduit and NEMA 3R outdoor pullbox on the exterior of the building.
4. Furnish and install approx 4,600' of 12ct SMF from HH 7-2 to fiber entry point at 1374 Deerpath and into building at the fiber panel location tbd.
5. Furnish and install (1) loaded SPH panel at 1374 Deerpath.
6. Prep newly installed 12ct cable on both ends.
7. Pull existing splice case at HH 7-2, open and splice fibers tbd.
8. Splice (12) fibers at the new SPH location in the traffic cab.
9. Perform Power meter testing of splice fibers.

Description	Hours / Qty	Unit	Rate	Cost
PROJECT MANAGER	8	Hours	\$105.00	\$840.00
Foreman Labor	32		\$105.00	\$3,360.00
Technician Labor	32		\$92.00	\$2,944.00
12F TINIFIBER CABLE SINGLE MODE RIBBON OSP MICRO-ARMOR	4,600	Feet	\$3.50	\$16,100.00
SPH Housing for 1 CCH Panel	1	Each	\$52.50	\$52.50
12 Fiber Singlemode Ribbon Pigtailed 3M with LC- UPC Connectors	1	Each	\$100.00	\$100.00
12 Fiber Singlemode LC UPC Insert Panel Corning Compatable Blue	1	Each	\$100.00	\$100.00
Subcontractor Fees	1	Each	\$120,770.00	\$120,770.00

Sub Total: \$144,266.50

Equipment & Labor Total: \$144,266.50

Notes

- no overtime or weekend work included
- does not include any permitting of engineering

We appreciate the opportunity to provide your company with a proposal and hope to work with you on this project. Should you have any questions or if we can be of further assistance, please call me at the number below.

Sincerely,

Chad Peterson
630-973-6147
National Technologies
5101 Thatcher RD
Downers Grove, IL 60515 cpeterson@ntitech.com

