

Bid 21-11
Fire Station No. 5 Driveway Improvements
Bid opening: February 24, 2021

ADDENDUM NO. 1
Page 1 of 3

TO: All Bidders

FROM: Engineering Division, City of Aurora

DATE: February 18, 2021

THIS ADDENDUM FORMS A PART OF THE BIDDING AND CONTRACT DOCUMENTS.

1. The size of the PCC Dumpster Pad has changed to 7.5' deep by 11' wide. There will not be barrier curb on the perimeter of the dumpster pad. Special Provision SP R-11 – PCC Dumpster Pad shall be changed to:

SP R.11 – PCC DUMPSTER PAD

The PCC dumpster pad shall be completely formed with lumber of 1½" nominal thickness and held securely in place with stakes.

The PCC dumpster pad shall be installed per the P.C.C. SIDEWALK REMOVAL AND REPLACEMENT, 5" special provision with the following modifications.

The dimensions of the pad shall be 7.5' deep by 11' wide and butt up against the existing PCC driveway as shown on the plans and as directed by the Engineer. The pad shall be installed so that it drains towards the driveway at approximately 2% or as directed by the Engineer.

The PCC dumpster pad shall be installed on 4" of CA-6 aggregate base. The concrete shall be 6" thick and contain welded wire fabric.

This work will be paid for at the contract unit price per SQUARE FOOT (SF) for PCC DUMPSTER PAD which price shall include all labor and equipment necessary to install CA-6 subbase material and placing the concrete pad as specified herein as well as disposal of the earth excavation at the spoil pile provided onsite.

2. The Dumpster Pad Screening with Gate shall be changed to an overall dimension of 6' deep by 10' wide. A 6' tall, 10' wide gate shall be provided. The fence posts shall be installed prior to the pad being poured and shall be set approximately 6" inside the outside edge of the pad. Special Provision SP R.12-Dumpster Pad Screening with Gate shall be changed to:

SP R.12 – DUMPSTER PAD SCREENING WITH GATE

The fencing around the dumpster enclosure shall be Ultra UAF-201 Flat Top STD Bottom Commercial with a 6' height as shown in the detail in the plans. The enclosure shall be approximately 6' deep by 10' wide. A 10' wide gate shall be provided across the center of the

Fire Station No. 5 Driveway Improvements
ADDENDUM NO. 1, PAGE 1 of 2

dumpster pad. The 3" x 3" X .125" wall posts shall be installed prior to pouring the pad so that the center of the posts are approximately 6" inside the edge of the pad and shall be backfilled with concrete per the manufacturer's recommendations. The gate shall be installed approximately 1' off the edge of the existing driveway. The gate shall be 6' high to match the fence height. The fence shall be installed per the manufacturer's recommendations. **The fence shall have ornamental black slats between the vertical fence slats to screen the material within the enclosure.**

This work will be paid for at the contract lump sum price (LS) for DUMPSTER PAD SCREENING WITH GATE and shall include all labor, equipment, and materials necessary in accordance with this provision.

3. A revised bid schedule is attached to address the square footage change of Pay Item 14 – PCC Dumpster Pad.

Sincerely,



John D. Hoffmann, P.E.
Engineering Coordinator
City of Aurora Engineering Division

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY FILLING OUT THE FOLLOWING AND SENDING AN ORIGINAL OR FAX COPY OF THIS SHEET TO THE CITY OF AURORA ENGINEERING DIVISION AT 630/256-3229 OR PREFERRABLY BY E-MAIL AT jhoffmann@aurora.il.us IMMEDIATELY UPON RECIEPT.

COMPANY NAME_____

SIGNATURE OF COMPANY REPRESENTATIVE_____



**Schedule of Prices
Fire Station No. 5
Driveway Improvements
Bid 21-11**

Route 730 Hill Avenue
County Kane
Local Agency City of Aurora

RETURN WITH BID

(For complete information covering these items, see plans and specifications)

Addendum No. 1					
NO.	ITEM	UNIT	QUANTITY	UNIT COST	AMOUNT
1	Earth Excavation	CY	120		
2	Geotechnical Fabric for Ground Stabilization - Undercut	SY	720		
3	Subbase Granular Material, Type B	Ton	220		
4	2" Mill and 2" HMA Replacement	SY	40		
5	PCC Driveway Removal and Replacement, 8"	SF	910		
6	PCC Driveway Removal and Replacement, 10"	SF	6,400		
7	PCC Driveway Welded Wire Fabric	SF	7,430		
8	PCC Sidewalk Removal and Replacement, 5"	SF	800		
9	Expansion Joint Repair & Seal	LF	80		
10	Contraction Joint Sawcut, Special	LF	45		
11	Combination PCC Curb and Gutter, B6.12 w/ 4" Agg Base	LF	55		
12	Combination PCC Curb and Gutter Removal and Replacement	LF	155		
13	Flag Pole Reinstallation	LSum	1		
14	PCC Dumpster Pad	SF	83		
15	Dumpster Pad Screening with Gate	LSum	1		
16	Seeding - Aurora Mix	SY	750		
17	Detector Loop, Type III	LF	75		
18	Drill Existing Handhole	EA	1		
19	Traffic Control and Protection	LSum	1		
20	Items Ordered by Engineer	Allowance	1	\$16,000.00	\$16,000.00
21	Inlet Protection	EA	3		
22	Non-Special Waste Disposal	Ton	50		
23	Special Waste Disposal	Ton	10		
Bidder's Total Proposal for Making Entire Improvements =					