

June 22, 2021

Quote #: Q-CHI-40496

Edward Cruz
City of Aurora
44 E. Downer Place
Aurora IL 60507
United States

RE: Copper Build Out Room in APD Budget

Mr. Cruz,

Thank you for the opportunity to submit the following proposal for the project referenced above.

Scope of Work

1. Furnish and install any j-hooks necessary where the existing cable ends.
2. Furnish and install approximately 16,000FT of Cat6A copper cable from the IT closet to the new build-out area.
3. Furnish and install (2) 48port Ortronics 10 gig patch panels in the existing rack in the IT room.
4. Furnish and install (64) Cat6A Ortronics jacks.
5. Furnish and install (7) 8 port stainless faceplates in the body cam room and (6) 2port faceplates in the other secure room.
6. Furnish and install labels on both ends of the cables.
7. All cabling will be secured to existing ladder rack with velcro.
8. Provide Fluke copper testing upon completion
9. Review, compile and submit test results upon completion.

Labor and Equipment Total:**\$21,601.00****Notes:**

- **This quote is budgetary and will need to be revised when final plans are released**
- **Work to be completed during normal working hours Monday through Friday**

We appreciate the opportunity to provide your company with a proposal and hope to work with you on this project. Should you have any questions or if we can be of further assistance, please call me at the number below.

Thank you,

Nate Schroeder
Project Manager
C: 630-294-0849
nschroeder@ntitech.com