

January 31, 2020

Quote #: Q-CHI-35245

Mike Baker  
City of Aurora  
44 E Downer Place  
Aurora IL 60507

RE: ATC-Panel re-position in data closet

Mr. Baker,

Thank you for the opportunity to submit the following proposal for the project referenced above.

### SCOPE:

1. Furnish and install approx. 300 LF of 12ct SMF from HH 31-3 to BNSF data closet inside of the ATC provide 50' slack coils at each HH.
2. Furnish and install (1) loaded 1U rack wall mount panel in data closet.
3. Prep new 12ct cable at HH and in the data closet.
4. Provide fusion splicing of (12) fibers in the new panel at the data closet.
5. Provide fusion splicing of (12) fibers in the case at HH 31-3
6. Cut old cable and pull out of duct and remove old panel from the data closet.
7. Provide OTDR and Power meter testing from City Hall to data closet.
8. Provide test results package including OTDR traces and PM results.
9. Provide new audit package of HH 31-3.

Description	Hours/Qty	Unit	Rate	Cost
Project Manager	2	Hours	\$105.00	\$210.00
General Foreman - ST	8	Hours	\$105.00	\$840.00
Foreman - ST	8	Hours	\$105.00	\$840.00
Splicer - ST	8	Hours	\$92.00	\$736.00
Truck-Standard	16	Hours	\$12.00	\$192.00
Trailer - Splicing	16	Hours	\$28.00	\$448.00
OTDR	8	Each	\$12.00	\$96.00
Loaded Panel	1		\$750.00	\$750.00
300' of 12ct SMF FOC	300		\$0.50	\$150.00

**Sub Total:** \$4,262.00

**Equipment & Labor Total:** \$4,262.00

We appreciate the opportunity to provide your company with a proposal and hope to work with you on this project. Should you have any questions or if we can be of further assistance, please call me at the number below.

Sincerley,

Chad Peterson



5101 Thatcher Rd, Downers Grove IL 60515

P: 630-852-7751/ Cell; 630-973-6147

Email: cpeterson@national-techs.com